

Additional pictures of block structures



Power meter picture – Wisconsin Public Service is utility company



Inside of one structure w/ generator



No pictures available of abandoned guy anchor pads

Regarding crane access, vendor will need to let you determine that. There is one picture showing tower with another tower and smaller structures toward bottom right of photo. Otherwise, vendors may need to plan on a site visit.

Tree removal – Removal of an agreed amount of trees to facilitate tower removal will be allowed.

How many abandoned guy wire anchor points are there?

There are 4 “footings”. During site visit, the anchor points were determined to be footings. Size is approximately 18”x18”. Depth unknown.

RFP#15-047-34 – Cedarville Tower Removal Addendum #1

Does removal of these guy wire anchor points constitute removing all of the buried concrete anchor in its entirety and backfill the vacancy after removal or just removal of anchor shafts and upper portion of concrete to below ground level and backfill over to level surface?

Complete removal is preferred. However, if footings are removed below the surface and backfilled, that is acceptable. Documentation of remaining footings will be required for future reference.

If complete removal of entire concrete anchors is required, what are the specs on underground concrete anchor points (size, width and depth, volume)?

There is no documentation.

Do you have detailed records or prints of installation of guy wire anchor points and also the same details for the tower foundation?

There is no documentation.